



## BOX STUD BEAM FOR LINTEL

THE CSJ STUD BOX BEAM SHALL BE STITCHED WITH SELF DRILLING SCREWS AT 2'-0" ON CENTERS. THE STUD BEAM SHALL BE ATTACHED TO THE COLUMNS WITH L3X3X $\frac{1}{4}$ " CLIP ANGLES, AT TOP AND BOTTOM OF THE STUD BEAM.



*C.V. Surendran*  
11-05-09

## SUPPLEMENTARY DRAWING NO. 110

REAGAN COUNTY IND. SCHOOL DISTRICT, BIG LAKE, TEXAS  
HIGH SCHOOL REMODELING, 2008 IMPROVEMENTS-PHASE II

<b>SC</b>	<b>SURENDRAN CONSULTING STRUCTURAL ENGINEERS</b>	
	8107 Kenosha Avenue	Phone: 806.793.8668
	Lubbock, TX 79423-1723	Fax: 806.795.1582
	www.surendranconsulting.com	

SHEET NO. 1 OF 1  
DATE: NOV. 05, 2009