

ADDENDUM

Owner Contractor
Architect Field

Project Name: NEW HIGH SCHOOL Addendum No.: **Four (4)**
Hale Center ISD Date: November 07, 2008
103 W. Cleveland Project No.: 07027
Hale Center, Texas 79041-1210

This addendum shall be considered part of the Contract Documents for the above mentioned project as though it has been issued at the same time and incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall govern and take precedence.

Bidders are hereby notified that they shall make any necessary adjustments in their estimates on account of this Addendum. It will be construed that each Bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

Item No. One: In the Specifications, Section 00030 – Notice to Bidders: Change paragraph 3 to read as follows:

3. Bids shall be addressed to:

**Hale Center ISD
c/o Grimes & Associates – CM Department
P.O. Box 65
21103 FM 179
Wolfforth, TX 79382
Facsimile #: 806-863-2479 or 806-863-3350**

Item No. Two: In the Specifications, Section 00100 – Instructions to Bidders: Change paragraph 4.7. to read as follows:

4.7. Bid Delivery: Bid proposals may be faxed, delivered or mailed to:

**Hale Center ISD
c/o Grimes & Associates – CM Department
P.O. Box 65
21103 FM 179
Wolfforth, TX 79382
Facsimile #: 806-863-2479 or 806-863-3350**

Item No. Three: In the Specifications, Section 01030 – Bid Packages: Add Bid Package 17B – Finish Hardware

17.1 This vendor shall furnish labor, materials, equipment, and services necessary to select, coordinate, and schedule, delivery of the complete finish hardware for doors as listed in the door schedules and as approved during the submittal process.

17.2 Types of finish hardware required include but is not limited to the following;

- Hinges
- Lock Cylinders
- Lock and Latch sets
- Thresholds
- Closures

17.3 Keying requirements as per specifications and school Superintendent security requirements. Delivery FOB Jobsite, removal of all shipping debris.

Item No. Four: In the Specifications, Section 08211 – Flush Wood Doors: For clarification purposes the doors and window lites will not be pre-finished.

Item No. Five: In the Specifications, Section 13122 – Pre-Engineered Metal Building systems: Make the following changes and/or specifications:

- A. For clarification purposes the roof purlin spacing shall be changed from 60” O.C. to 48 “ O.C. at all locations except for Gymnasium & Locker rooms.
- B. For clarification purposes the roof deck at Gym shall be Epic metal Corporation’s ER2RA 20 gauge acoustic deck. The deck shall be supported by roof purlins at spacing of 5’-0” O.C.
- C. For clarification purposes Acoustical Deck is to be factory primed.

Item No. Six: General Items: For clarification purposes make the following changes and/or revisions:

- A. The millwork, elevation 01/A25, in all classrooms shall be bid under Alternate #5. Classroom Wardrobes, elevation 05/A25, are to be included in Base Bid.
- B. The acoustical insulated walls tight to deck shall to be fire taped only.
- C. The Caulking for the EIFS shall be included in Bid Package #27 – Painting and Finishing
- D. The Caulking of flashings/copings shall be included in Bid Package #28 – Single Ply Roofing.
- E. Door 20 to BAND HALL C19 shall be SCTF Acoustical not HM.

Item No. Seven: In the Drawings, Sheet A2 – Floor Plan Area “A” , For clarification purposes make the following changes and/or revisions:

- A. NET A16 - change the ceiling from a 2’x2’ Lay-in at 9’-0” to exposed structure (Painted).
- B. VEST. C01 – change the ceiling from exposed structure to a 2’x2’ Lay-in Type I @ 10’-0”.
- C. CORRIDOR C02 – Change the ceiling from exposed structure to a 2’x2’ Lay-in Type I @ 10’-0”.

Item No. Eight: In the Drawings, Sheet A4 – Floor Plan Area “C”, For clarification purposes make the following changes and/or revisions:

- A. COMMONS C03 – Change the ceiling from Gyp. Bd. to a 2’x2’ Lay In Type I sloping with the structure and Gyp. Bd. Furr outs around the beams.
- B. BAND HALL C19 – Change the ceiling height from 8’-0” to 17’-0”.

Item No. Nine: In the Drawings, Sheet A5 – Floor Plan Area “D”, For clarification purposes make the following changes and/or revisions:

- A. GYMNASIUM D01 – The perimeter steel base angle is part of the wood flooring work and the wood floor contractor’s responsibility.
- B. GYMNASIUM D01 – The steel rail for the visitor seating will be field finished and match the home side if Alternate #4 is accepted.

Item No. Ten: In the Drawings, Sheet A6 – Agricultural Shop, For clarification purposes make the following changes and/or revisions:

- A. AG. SHOP 001 – Drywall partitions are to be enamel paint, color by architect.
- B. CLASSROOM 007, AG. OFF. 008, & CLASSROOM 010 – Change the ceiling from exposed structure to a 2’x2’ Lay In Type I @ 9’-0”

C. There will be two Overhead Doors #24 on the Northeast Wall , one each between Grid Lines 4 & 5 and 5 & 6 if Alternate # 8 is accepted.

Item No. Eleven: In the Drawings, Sheet A8 & Sheet A9 – Exterior Elevations, For clarification purposes provide a 3/8” masonry control joint at each side of all openings in the exterior masonry walls..

Item No. Twelve: In the Drawings, Sheet A18 - Reflected Ceiling Plan – Area “D”, FIRE D35, For clarification purposes the ceiling needs to be changed from a Gyp. Bd. Ceiling to Exposed Structure (Painted) as shown on the Finish Schedule.

END OF ADDENDUM