

ADDENDUM

Owner Contractor
Architect Field

Project Name: High School HVAC
Silverton I.S.D.
700 Loretta Street
Silverton, Texas 79257

Addendum No.: **Two (2)**
Date: August 10, 2009
Project No.: 09098.1

This addendum shall be considered part of the Contract Documents for the above mentioned project as though it has been issued at the same time and incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall govern and take precedence.

Bidders are hereby notified that they shall make any necessary adjustments in their estimates on account of this Addendum. It will be construed that each Bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

General Items:

Item No. One: In the Specifications, Section 01010- Summary of Work: for clarification purposes the following sequence of operation should be followed;

1.5 Construction after school has begun;

- 1.5.1 Have all new exterior work (gas and electric) in-place and ready for connection to new equipment and existing utilities with a minimal amount of down time.
- 1.5.2 Ensure all concrete pads for new wall mount unit support frames are in-place and ready for new equipment.
- 1.5.3 Coordinate with school to take possession of one, first floor classroom at a time. Install window infill and new equipment completely before moving to next room. Coordinate with owner for finish colors.
- 1.5.4 Coordinate with school before making any roof penetrations or curb cuts as to minimize the amount of disturbance to teachers and students. Ensure roof penetrations are weather tight.
- 1.5.5 Coordinate with school before placing new furnace and coils on second floor in-place.

END OF ADDENDUM